

## 臺南市政府小型工程單價表

附件二

項次	工項	單位	單價	備註
1	路面工程			
1.1	AC路面			
1.1.1	5cm厚 AC路面	M2	350	
1.1.2	10cm厚 AC路面	M2	730	
1.2	PC路面			
1.2.1	15cm厚 PC路面	M2	400	
1.2.2	20cm厚 PC路面	M2	500	
1.3	級配路面			
1.3.1	15cm厚級配路面	M2	210	
1.3.2	30cm厚級配路面	M2	380	
1.4	AC+級配路面			
1.4.1	5cm厚 AC+15cm厚級配路面	M2	580	
1.4.2	5cm厚 AC+30cm厚級配路面	M2	750	
1.4.3	5cm厚 AC+30cm厚級配路面 +50cm厚回填土方	M2	900	
2	擋土牆 (護岸)			
2.1	重力式擋土牆 (護岸)			
2.1.1	重力式擋土牆 H=1M	M	2,400	
2.1.2	重力式擋土牆 H=2M	M	5,600	
2.1.3	重力式擋土牆 H=3M	M	9,500	
2.2	懸臂式擋土牆 (護岸)			
2.2.1	懸臂式擋土牆 H=3M	M	12,500	
2.2.2	懸臂式擋土牆 H=4M	M	17,500	
2.2.3	懸臂式擋土牆 H=5M	M	23,000	
2.2.4	懸臂式擋土牆 H=6M	M	30,000	
2.2.5	懸臂式擋土牆 H=7M	M	39,000	
2.2.6	懸臂式擋土牆 H=8M	M	49,500	
2.2.7	懸臂式擋土牆 H=9M	M	69,000	
2.2.8	懸臂式擋土牆 H=10M	M	79,000	
3	排水溝			
3.1	矩形暗溝			
3.1.1	40cm*60cm矩形暗溝	M	7,900	
3.1.2	60cm*80cm矩形暗溝	M	9,300	
3.1.3	100cm*100cm矩形暗溝	M	12,100	
3.1.4	120cm*120cm矩形暗溝	M	13,500	
3.2	U形暗溝			
3.2.1	40cm*60cm U形暗溝	M	7,700	
3.2.2	60cm*80cm U形暗溝	M	9,300	
3.2.3	100cm*100cm U形暗溝	M	13,100	
3.2.4	120cm*120cm U形暗溝	M	15,200	
3.3	矩形明溝			
3.3.1	60cm*80cm矩形明溝	M	4,025	
3.3.2	60cm*100cm矩形明溝	M	5,640	

項次	工項	單位	單價	備註
3.3.3	60cm*120cm矩形明溝	M	6,480	
3.3.4	70cm*80cm矩形明溝	M	4,170	
3.3.5	70cm*100cm矩形明溝	M	5,770	
3.3.6	70cm*120cm矩形明溝	M	6,620	
3.3.7	80cm*80cm矩形明溝	M	4,220	
3.3.8	80cm*100cm矩形明溝	M	5,890	
3.3.9	80cm*120cm矩形明溝	M	6,740	
3.3.10	100cm*100cm矩形明溝	M	7,060	
3.3.11	100cm*150cm矩形明溝	M	9,180	
3.3.12	120cm*120cm矩形明溝	M	8,030	
3.3.13	120cm*150cm矩形明溝	M	9,600	
3.3.14	150cm*150cm矩形明溝	M	9,850	
3.3.15	150cm*200cm矩形明溝	M	12,130	
3.3.16	200cm*150cm矩形明溝	M	10,580	
3.3.17	200cm*200cm矩形明溝	M	12,870	
<b>3.4</b>	<b>U形明溝</b>			
3.4.1	40cm*60cm U形明溝	M	3,200	
3.4.2	60cm*80cm U形明溝	M	4,500	
3.4.3	100cm*100cm U形明溝	M	7,600	
3.4.4	120cm*120cm U形明溝	M	9,400	
<b>4</b>	<b>集水井</b>			
4.1	80cm*80cm*80cm集水井	座	16,000	
4.2	80cm*80cm*100cm集水井	座	17,500	
4.3	80cm*80cm*120cm集水井	座	19,500	
4.4	80cm*80cm*150cm集水井	座	22,450	
4.5	100cm*100cm*100cm集水井	座	24,150	
4.6	100cm*100cm*120cm集水井	座	25,400	
4.7	100cm*100cm*150cm集水井	座	30,000	
4.8	100cm*100cm*250cm集水井	座	42,400	
4.9	100cm*100cm*300cm集水井	座	53,700	
4.10	100cm*100cm*350cm集水井	座	60,800	
4.11	150cm*150cm*120cm集水井	座	36,500	
4.12	150cm*150cm*150cm集水井	座	40,600	
<b>5</b>	<b>蛇籠</b>			
5.1	甲種蛇籠60cm*100cm	M	1,000	
5.2	乙種蛇籠40cm*67cm	M	900	
5.3	箱籠石籠1M*1M	M	2,100	
<b>6</b>	<b>護欄</b>			
6.1	護欄塊	塊	1,400	
6.2	紐澤西護欄	M	2,200	
<b>7</b>	<b>單孔箱涵</b>			
<b>7.1</b>	<b>120cm*120cm單孔箱涵</b>			
7.1.1	120cm*120cm單孔箱涵覆土深度0m	M	12,500	
7.1.2	120cm*120cm單孔箱涵覆土深度1m	M	13,000	
7.1.3	120cm*120cm單孔箱涵覆土深度2m	M	13,500	

項次	工項	單位	單價	備註
7.1.4	120cm*120cm單孔箱涵覆土深度3m	M	14,000	
7.1.5	120cm*120cm單孔箱涵覆土深度4m	M	15,000	
<b>7.2</b>	<b>150cm*150cm單孔箱涵</b>			
7.2.1	150cm*150cm單孔箱涵覆土深度0m	M	20,000	
7.2.2	150cm*150cm單孔箱涵覆土深度1m	M	21,000	
7.2.3	150cm*150cm單孔箱涵覆土深度2m	M	21,500	
7.2.4	150cm*150cm單孔箱涵覆土深度3m	M	22,000	
7.2.5	150cm*150cm單孔箱涵覆土深度4m	M	23,000	
<b>7.3</b>	<b>200cm*200cm單孔箱涵</b>			
7.3.1	200cm*200cm單孔箱涵覆土深度0m	M	26,000	
7.3.2	200cm*200cm單孔箱涵覆土深度1m	M	27,000	
7.3.3	200cm*200cm單孔箱涵覆土深度2m	M	27,500	
7.3.4	200cm*200cm單孔箱涵覆土深度3m	M	28,500	
7.3.5	200cm*200cm單孔箱涵覆土深度4m	M	29,000	
<b>7.4</b>	<b>220cm*220cm單孔箱涵</b>			
7.4.1	220cm*220cm單孔箱涵覆土深度0m	M	29,000	
7.4.2	220cm*220cm單孔箱涵覆土深度1m	M	29,500	
7.4.3	220cm*220cm單孔箱涵覆土深度2m	M	30,000	
7.4.4	220cm*220cm單孔箱涵覆土深度3m	M	31,000	
7.4.5	220cm*220cm單孔箱涵覆土深度4m	M	31,500	
<b>7.5</b>	<b>250cm*250cm單孔箱涵</b>			
7.5.1	250cm*250cm單孔箱涵覆土深度0m	M	32,500	
7.5.2	250cm*250cm單孔箱涵覆土深度1m	M	33,000	
7.5.3	250cm*250cm單孔箱涵覆土深度2m	M	34,000	
7.5.4	250cm*250cm單孔箱涵覆土深度3m	M	34,500	
7.5.5	250cm*250cm單孔箱涵覆土深度4m	M	35,500	
<b>7.6</b>	<b>300cm*300cm單孔箱涵</b>			
7.6.1	300cm*300cm單孔箱涵覆土深度0m	M	49,000	
7.6.2	300cm*300cm單孔箱涵覆土深度1m	M	49,500	
7.6.3	300cm*300cm單孔箱涵覆土深度2m	M	50,500	
7.6.4	300cm*300cm單孔箱涵覆土深度3m	M	51,500	
7.6.5	300cm*300cm單孔箱涵覆土深度4m	M	52,500	
<b>8</b>	<b>清除坍方</b>			
8.1	人工清除坍方土方	M3	190	人工搬運20M以內
8.2	人工清除坍方軟石	M3	550	人工搬運20M以內，Φ0.3M以下
8.3	人工清除坍方堅石	M3	1,120	人工搬運20M以內，Φ0.3M以上
8.4	機械清除坍方堅石	M3	70	含石率10%以下
8.5	機械清除坍方堅石	M3	130	含石率10~50%
8.6	機械清除坍方堅石	M3	220	含石率50%以上
<b>9</b>	<b>回填借用土方</b>			
9.1	機械填借用土方	M3	300	運距12KM計
9.2	機械填混合料	M3	320	運距12KM計
<b>10</b>	<b>涵管</b>			
10.1	Φ50cm涵管	支	5,300	B型三級管(2.4M/支)
10.2	Φ90cm涵管	支	8,300	B型三級管(2.4M/支)

項次	工項	單位	單價	備註
10.3	Φ100cm涵管	支	14,300	B型三級管(2.4M/支)
10.4	Φ120cm涵管	支	20,300	B型三級管(2.4M/支)
10.5	Φ150cm涵管	支	29,800	B型三級管(2.4M/支)
10.6	Φ200cm涵管	支	56,600	B型三級管(2.4M/支)
<b>11</b>	<b>打樁</b>			
11.1	打Φ25CM*6M RC樁	支	7,700	擋土牆及護岸基礎用
11.2	打鋼軌樁37KG/M	M	1,900	
11.3	打鋼軌樁42KG/M	M	2,200	
<b>12</b>	<b>消波塊</b>			
12.1	5T消波塊	個	12,500	
12.2	10T消波塊	個	20,700	
12.3	15T消波塊	個	27,600	
12.4	20T消波塊	個	35,700	
12.5	25T消波塊	個	43,200	
<b>13</b>	<b>加勁擋土牆</b>			
13.1	加勁擋土牆(高度5M)	M2	6,100	
13.2	加勁擋土牆(高度7M)	M2	8,350	
<b>14</b>	<b>植生</b>			
14.1	撒草籽(覆稻草蓆)	M2	100	
14.2	掛網客土噴植(厚度5CM)	M2	420	
14.3	自由樑框掛網噴植(厚度5CM, 錨釘3M)	M2	1,500	
14.4	型框邊坡噴植	M2	2,300	
<b>15</b>	<b>拍漿溝</b>			
15.1	鋪網噴混凝土溝(寬1M深35CM厚10CM)	M	1,950	
<b>16</b>	<b>預力地錨</b>			
16.1	30T預力地錨	M	3,000	
16.2	40T預力地錨	M	3,200	
16.3	60T預力地錨	M	4,300	
<b>17</b>	<b>防砂壩</b>			
17.1	防砂壩(高3M, 頂寬2M)	M	46,100	
17.2	防砂壩(高4M, 頂寬2M)	M	62,100	
17.3	防砂壩(高5M, 頂寬2M)	M	80,500	
17.4	防砂壩(高6M, 頂寬2.5M)	M	120,400	
17.5	防砂壩(高7M, 頂寬2.5M)	M	151,600	
17.6	防砂壩(高8M, 頂寬2.5M)	M	182,700	
17.7	防砂壩(高9M, 頂寬2.5M)	M	206,600	
17.8	防砂壩(高10M, 頂寬2.5M)	M	230,500	
<b>18</b>	<b>固床工</b>			
18.1	固床工(高1.5M, 頂寬0.5M)	M	4,800	
18.2	固床工(高1.5M, 頂寬1M)	M	8,300	
18.3	固床工(高2M, 頂寬1M)	M	12,100	
18.4	固床工(高3M, 頂寬1M)	M	20,900	